


GENERAL NOTES



• "---" indicates the feature is not an option for this model and/or the data is not yet available.



SHIPPING WEIGHT		
Case	Weight	
OWZGGQA		



COMPONENT ALL MEASUREMENTS ARE TAKEN PER ASHRAE-72-2005 SPECIFICATIONS. HILLPHOENIX REFRIGERATED DISPLAY CASES FOR SALE IN THE UNITED STATES MEET OR EXCEED DEPARTMENT OF ENERGY 2017 REQUIREMENTS.

Rev. Date	Rev. #	Rev. Title
3-30-20	1	OPTIONS UPDATE
03-16-20	0	SOLOCHILL V4







ELECTRICAL DATA

		High Efficiency Fans			ndensate aters
Case	Fans Per	120 Volt		120	Volts
Length	Case	Amps	Watts	Amps	Watts
12'	3	0.18	14.0	2.10	253.0

DEFROST CONTROLS

		Elect	ric Defrost
Defrosts Per Day	Run Off Time (Min)	Fail Safe (Min)	Termination Temp (°F)
3	5	50	45

NOTES

- "---" indicates that the feature is not an option on this case model and/or the data is not yet available.
- Listed discharge air velocity represents the average velocity at the peak of defrost.
- Temperature and defrost settings listed above are recommended start-up settings. Final operational settings may need to be adjusted for the store conditions in which the case operates.



COMPONENT ALL MEASUREMENTS ARE TAKEN PER ASHRAE-72-2005 SPECIFICATIONS. HILLPHOENIX REFRIGERATED DISPLAY CASES FOR SALE IN THE UNITED STATES MEET OR EXCEED DEPARTMENT OF ENERGY 2017 REQUIREMENTS.

Rev. Date	Rev. #	Rev. Title
3-30-20	1	OPTIONS UPDATE
03-16-20	0	SOLOCHILL V4



Wide Single-Deck Island Merchandiser 12' Frozen Food



S	Ο	10	6	1	-	I	L	TM.
$\mathbf{\nabla}$	$\mathbf{\nabla}$		MIC					

SOLOCHILL DATA			@95° Condensin	g Temperature	
Volts	Phase Frequency		Wire		
208	1	60	3 Wire + Ground		
Case Length	Evapo	rator Temp (°F)	Discharge Air (°F)	Discharge Air Velocity (FPM)	
12'		-22	-15	345	

Case			R4	48A		
Length	Condensing Unit Model	MCA	MOP	Required Capacity	THR (BTUH)	Flow Rate
12'	DA420	36.4	40	6516	10452	3.0




COMPONENT ALL MEASUREMENTS ARE TAKEN PER ASHRAE-72-2005 SPECIFICATIONS. HILLPHOENIX REFRIGERATED DISPLAY CASES FOR SALE IN THE UNITED STATES MEET OR EXCEED DEPARTMENT OF ENERGY 2017 REQUIREMENTS.

Rev. Date	Rev. #	Rev. Title
3-30-20	1	OPTIONS UPDATE
03-16-20	0	SOLOCHILL V4












ALL MEASUREMENTS ARE TAKEN PER ASHRAE-72-2005 SPECIFICATIONS. HILLPHOENIX REFRIGERATED DISPLAY CASES FOR SALE IN THE UNITED STATES MEET OR EXCEED DEPARTMENT OF ENERGY 2017 REQUIREMENTS.

Rev. Date	Rev. #	Rev. Title
3-30-20	1	OPTIONS UPDATE
03-16-20	0	SOLOCHILL V4



OWZGGQA





NOTES

- * :STUB-UP AREA
- ** :RECOMMENDED STUB-UP CENTERLINE FOR ELECTRICAL AND HUB DRAINS
- · Ends add approximately 1" to case height.



ALL MEASUREMENTS ARE TAKEN PER ASHRAE-72-2005 SPECIFICATIONS. HILLPHOENIX REFRIGERATED DISPLAY CASES FOR SALE IN THE UNITED STATES MEET OR EXCEED DEPARTMENT OF ENERGY 2017 REQUIREMENTS.

Rev. Date	Rev. #	Rev. Title
3-30-20	1	OPTIONS UPDATE
03-16-20	0	SOLOCHILL V4

